T2 Construction, Inc.

T2

City Park
Horseshoe Court Renovation

Owner: Denver Parks and Recreation Department
C/O: Adrienne Burton
adrienne.burton@denvergov.org

Contact: Stuart Cameron
Date: September 28, 2015

Location: Denver, Co

Bid Item #	Bid Item Description	Quantity	Unit	Unit Price	Total
1.00	Mobilization and General Conditions	1.00	ls		3,210.00
2.00	Remove Chainlink Fence	160.00	lf	5.00	800.00
3.00	Remove Asphalt	800.00	sf	1.80	1,440.00
4.00	Remove Horseshoe Pit Stakes	10.00	each	30.00	300.00
5.00	Remove Backboards and buried boards	10.00	each	75.00	750.00
6.00	Site Grading	1.00	ls	1,480.00	1,480.00
7.00	Install Concrete Curb 8" wide 6" deep	100.00	lf	18.00	1,800.00
8.00	Install Concrete Flatwork 4" depth	1,340.00	sf	7.50	10,050.00
9.00	Install Backboards	10.00	each	280.00	2,800.00
10.00	Install Horseshoe Stakes	10.00	each	190.00	1,900.00
11.00	Install Pit Clay 8" depth	10.00	each	150.00	1,500.00
12.00	Install New Crusher Fines 3" Depth average	3,020.00	sf	1.05	3,171.00
13.00	Adjust Irrigation	1.00	ls	425.00	425.00
15.00	Remove Sandblast and Paint Benches	4.00	each	600.00	2,400.00
	Total Cost of Proposal				32,026.00

Work can be scheduled after October 15, 2015
Pricing is good for 60 days to award contract

5435 West 59th Ave, Arvada, CO 80003
(303) 432-8742 * Fax (303) 432-8806
An Equal Opportunity Employer